BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE –'B'

Item-52

Name of Work:-Construction of culverts best county-II and surrounding areas in ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.Vijayakumar R (C K CONSTRUCTIONS)	
				Rate	Rate in Words
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	92.40	250.00	Rupees Two Hundred Fifty Only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.3 of PWD SR 2018-19	Cum	13.20	5000.00	Rupees Five Thousand Only
3	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 25 / Item No. 5.6, PWD SR 2018-19	Cum	47.52	4100.00	Rupees Four Thousand One Hundred Only
4	KSRB 15.1.2 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:4, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications Page No. 115 / Item No. 15.2, PWD SR 2018-19	Sqm	79.20	108.10	Rupees One Hundred Eight and Paise Ten Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.Vijayakumar R (C K CONSTRUCTIONS)	
				Rate	Rate in Words
5	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery,	Cum	19.80	5400.00	Rupees Five Thousand Four Hundred Only
6	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - Data rate	Sqm	79.20	5000.00	Rupees Five Thousand Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.